

Spray Facility (ADAS)

Gary Page
Loughborough University


Multiphase Wind Tunnel (ADAS spray facility)

Gary Page

Department of Aeronautical and Automotive Engineering

Loughborough University

G.J.Page@lboro.ac.uk





2 April 2025

Why a New Multiphase Wind Tunnel?

- ▶ Modern cars depend upon sensors
 - ▶ Radar, Lidar, optical cameras, ultrasonic
- ▶ Degrade in poor weather, particularly rain
 - ▶ May not see a vehicle, cyclist or pedestrian
 - ▶ May 'hallucinate' another vehicle (especially lidar in high rainfall intensity)
- ▶ Previous work at Loughborough and elsewhere assume a given spray distribution
 - ▶ Little knowledge of the actual mechanisms for source generation and spray characterisation
 - ▶ Can then be used as boundary conditions for simulations

'The Influence of Automotive Aerodynamics on Spray Transport and the Implications for ADAS Sensor Operability,' PhD thesis, Conor Crickmore, 2024.


<https://doi.org/10.26174/thesis.lboro.26861788.v1>



Overall Design Parameters

- ▶ Single full size wheel and tyre 235/55 R16 with correct load
- ▶ *Sub-scale quarter car (single wheel) and full car (four wheels)*
- ▶ *Isolated Formula 1 model wheel (60% scale)*
- ▶ Running on a belt 2m long and 0.7m wide
- ▶ Air and belt speed up to 30 m/s (67 mph, motorway speed)
- ▶ Up to 2mm film of water ahead of wheel (target 15 litres/second)
- ▶ Measure near field source droplet and flow field
- ▶ Measure far field droplet and flow field
- ▶ Real ADAS sensors in operation
- ▶ Total budget ~£1.2M

Overview




CFD Velocity Magnitude


Nozzle Velocity 39 m/s

Reported fan pressure drop 800-850 Pa


6 x 10kW fans



CFD Velocity Magnitude




CFD Total Pressure




CFD Streamlines from Fans

30 s to recirculate



CFD Streamlines from Contact Patch



Status

- ▶ Preliminary design hand calculations and CFD consistent
- ▶ Need to refine further and look at water extraction
- ▶ Delayed by Facilities Management
 - ▶ room strip-out and refurbishment yet to start
- ▶ Building proof of concept belt and water system in separate lab
- ▶ Final belt will be built and constructed in separate lab and moved when building released (September 2025?)
- ▶ New highly experienced Research Fellow about to start
- ▶ Plan to take measurements in Summer 2027